- 1.8m high treated close boarded timber fence
- 1.8m high 215 brick wall in facing brick as housing
- Hanson Formpave permeable paving.
- 450x450 riven faced paving slabs with gravel joints. (nom. 900 path to all house perimeters)
- Turf
- Shrub planting to schedule.
- Low hedge as schedule
- Trees

Trees:

Rowan (Sorbus aucuparia) 2.75-3.0m 8-10cm girth
Wild Cherry (Prunus avium) 2.75-3.0m 8-10cm girth
Alder (Alnus glutinosa) 2.75-3.0m 8-10cm girth
Crab Apple (Malus sylvestris) 2.75-3.0m 8-10cm girth
Whitebeam (Sorbus aria) 2.75-3.0m 8-10cm girth

Indigenous Hedging Species:

Hawthorn (Crataegus monogyna)
Hazel (Corylus avellana)
Holly (Ilex aquifolium)
Guelder Rose (Viburnum opulus)

Planted in double staggered rows 600-900 whips.

Landscaping shrubs:

Hebe Autumn Glory: 30-40 cm 4/m2
Buddleia "White Cloud" 60-80 cm 3/m2
Lavandula angustifolia vera 30-40cm 4/m2
Lonicera periclymenum 30-40cm 4/m2.



CHORLEY BOROUGH COUNCIL
- 1 SEP 2009
CHORLEY BOROUGH COUNCIL
- 3 AUG 2009
THIS IS THE PLAN REFERRED TO IN
APPLICATION No. 09/00711

A2

REVISION A. TREE, HEDGES & LANDSCAPING SPECIES AMENDED 09/2009

Elemoss Designs Ltd.
13 Keller Drive,
Worsley,
Manchester, M28 7TU
phone/fax 0161 799 5133
Architectural Design and Development Consultancy.

Project: 4 EWELL CLOSE CHORLEY PR6 8TT	Title: LANDSCAPING	Date: 19/6/09	Drawn by: BC
	Client: D BROWN	Scale: 1:100	Date: 08/09

(1).