



Our Ref: ECCLESTON/APR13/POSTAL/CH1941

03 May 2013

Mr. A. Platt, Clerk to the Council
Eccleston Parish Council
9 Ambleside Avenue
Euxton, Chorley
PR7 6NX

Dear Alan

ECCLESTON PARISH COUNCIL MUGA

Lightmain would like to thank Eccleston Parish Council for the opportunity to tender for the above project and we are pleased to provide our quotation along with the following documents in support of our submission. As requested, we have also provided the information on CD in pdf format.

Completed Project Management document incorporating:

- Form of Tender
- Anti-Collusion Certificate

Design Proposals/Associated Graphics

Proposal for dealing with potential drainage issues

Proposed Programme of Work & Timescales

Health & Safety Plan & Method Statements (Appendix I)

Key Worker Information (Appendix II)

Guarantees/Warranties/Specifications/Maintenance (Appendix III)

Company Profile/Background Information (Appendix IV)

Please note that our prices reflect our **highest specification** and the use of the best quality materials which means that the facility will endure the rigorous usage for which it is intended long after other courts constructed from lower grade steel or chain link fencing have needed to be replaced. If, however, you are offered what seems to be an equivalent specification at a lower price, please allow us to detail any differences in specification and consider offering a similar solution that could match that price. We would recommend that before making a final decision on the choice of supplier that you compare sample MUGA fencing from each of the companies who have been invited to tender. We believe that the quality of our products and services are second to none.

Unlike some of our competitors who import lower grade steel product from the Far East and Eastern Europe, Lightmain's heavy duty MUGA's are made in Britain from materials sourced in Britain at our own fabrication facility in Rotherham and are top of the range for quality. The integrity of our steelwork carries a fair wear and tear warranty of 25 years.

We also have our own powder coating facility which means that with the extra processes Lightmain has introduced over and above standard powder coating processes that we can offer a 5 year warranty on the paint finish.

Manufacturing our own products also means that we are able to offer a bespoke service to suit our clients' specific needs.



Lightmain Company Limited, Hibbard Works, Station Road, Wath-upon-Deane, Rotherham, S63 7DG
Tel: 01709 763410 Fax: 01709 763411 Email: sales@lightmain.co.uk Web: www.lightmain.co.uk
Reg No. 2642662





Lightmain was awarded the MoD Defence Estates contract for MUGAs across military establishments following a rigorous selection process which involved 14 companies. Lightmain's success was primarily based on quality, durability of product and value for money. In addition, a Lightmain MUGA facility is used as an example of excellence by RoSPA for their 2 day operational training courses.

Please also note that our projects are installed by our own **directly employed staff** which means that we have total control over both the quality of the installation and the timescale for completion.

It may also be of interest to know that in recognising that our work brings us into contact with the young and vulnerable, all of our staff have been List 99 and CRB checked.

I hope that I have covered everything that you need for the moment, but, should you have any queries or require any additional information please do not hesitate to contact me.

Yours sincerely

Trevor Lafferty
Managing Director
LIGHTMAIN COMPANY LIMITED



Lightmain Company Limited, Hibbard Works, Station Road, Wath-upon-Deane, Rotherham, S63 7DG
Tel: 01709 763410 Fax: 01709 763411 Email: sales@lightmain.co.uk Web: www.lightmain.co.uk
Reg No. 2642662





**ECCLESTON PARISH COUNCIL
LIGHTMAIN REFERENCE CH/1941**

GROUNDWORKS (As Item 4.1) £25,270.00
We are able to offer a £2,000.00 discount for retaining spoil on site **£23,270.00**

SOAKAWAYS/DRAINAGE (As Item 4.2) **£ 4,000.00**

PATHS (As Item 4.3) **£ 2,000.00**

CABLEDUCT (As Item 4.4) included in Lighting costs

FENCING FOUNDATIONS (As Item 4.5) included in MUGA costs

**MUGA (As Item 4.6) – Sample fencing will delivered 07.05.14
28m x 14m x 3m high heavy duty MUGA consisting of:**

- 781 lin.m x 3m high Lightmain heavy duty true rebound fencing with straining posts to reduce noise/panel reverberation (See appended Appendix III for specifications/noise reduction measurement tests)
 - 2 no curved back DDA compliant open goals
 - Curved corners
 - 1 no chicane
 - Tennis/Volleyball net complete with post fixings **£32,256.40**
- Discount 10%** - Total (supplied and installed) **£29,307.50**



Optional integrated pod seating additional £1,800.00 each

LIGHTING (As Item 4.7) consisting of:

- 4 no unique Lightmain integrated mid-hinged 6.7m high columns
- 8 no x 400watt Halide sports floodlights
- Electrical distribution unit, photocell and timer arrangement
- Connection to existing community building
- Ducting as per tender spec (See Appendix III for specifications/photographs of previous installations)

NB. This lighting spec provides the following output which exceeds the tender specification:

- Average illuminance of 200 lux
- Uniformity of 0.71
- Maintenance factor of 0.8

£17,400.00

ELECTRICAL (As Item 4.8) included in Lighting costs

LINE MARKING (As Item 4.9) **£ 600.00**

ACCESSORIES (As Item 4.10)

Tennis/Volleyball net included in MUGA costs

Plaque (left) incorporating Council crest and wording tbc **£ 350.00**

Plaque (right) incorporating Youth Centre logo and wording tbc **£ 500.00**

TOTAL FOR PROJECT (assuming retention of spoil on site) **£77,427.50**

All prices are subject to VAT at rate prevailing at time of invoice



Lightmain Company Limited, Hibbard Works, Station Road, Walth-upon-Deerne, Rotherham, S63 7DG
 Tel: 01709 763410 Fax: 01709 763411 Email: sales@lightmain.co.uk Web: www.lightmain.co.uk
 Reg No. 2642662





DRAINAGE

In order to ensure that the new facility will adequately drain, Lightmain will carry out the following procedures:-

- Set the new ballcourt surface to a crossfall. Fall between 1:80 and 1:100
- Insert a perforated pipe (as per tender spec) to collect excess water
- Pipe to lead into a constructed soakaway pit which will incorporate an inspection chamber cover (for safety reasons)
- The specification of the tarmac will be an open graded construction which will allow any standing water to be absorbed through the surface

ADDITIONAL BENEFITS OFFERED

- Discount of £2,000.00 on groundworks cost for retention of spoil on site
- 10% discount on standard MUGA costs
- Mid hinged lighting columns integrated into MUGA fenceline enabling easier mowing access around installation
- Optional extra of integrated pod seating at budget price
- Integrated tennis/volleyball facility providing additional play value

ENVIRONMENTAL BENEFITS

During the construction phase, Lightmain ensures minimal impact to the environment by taking the following steps.

- Carry out a tree protection plan and confirm a suitable access route for vehicles
- Consider any existing features of the site prior to commencement
- Minimise any noise by co-ordinating deliveries and excavations within a 9 – 5 time period
- Source locally produced materials to ensure a low carbon footprint
- All of Lightmain's products are manufactured from UK sourced (Sheffield) steel and produced in our purpose built factory in Rotherham (South Yorkshire)
- Any excavations will be reused wherever possible on site to avoid unnecessary landfill waste



Lightmain Company Limited, Hibbard Works, Station Road, Wath-upon-Deane, Rotherham, S63 7DG
Tel: 01709 763410 Fax: 01709 763411 Email: sales@lightmain.co.uk Web: www.lightmain.co.uk
Reg No. 2642662



PROGRAMME OF WORKS

ID	Description of Works	Pre Start	WEEK 1					WEEK 2					WEEK 3					WEEK 4						
			Mo	Tu	We	Th	Fr	Mo	Tu	We	Th	Fr	Mo	Tu	We	Th	Fr	Mo	Tu	We	Th	Fr		
	Award of Contract by client	█																						
	Pre contract meeting to discuss works and specification	█																						
	Allowance of 6-8 weeks for planning award	█																						
	Pre start meeting on site	█																						
	Setting out & site establishment		█																					
	Site clearance and excavations including cable trenches and drainage		█	█	█	█	█																	
	Install MUGA pcc edge and MOT type 1 stone base				█	█	█	█																
	Install base course tarmac						█	█	█															
	Install pathways						█	█	█															
	Install MUGA posts							█	█	█														
	Complete electrical cabling works to supply								█	█	█													
	Install wearing course tarmac									█	█	█												
	Install MUGA panels and signage									█	█	█	█	█	█									
	Complete electrical connection and test															█								
	Remodel spoil on site																█	█	█					
	Line markings																	█	█					
	Reinstatement and planting																		█	█				
	Post installation inspection																					█		
	Handover to Ecclestone Parish Council																						█	
	Weekly site progress meetings		█					█						█						█				█

Extension to Proposed Programme of Works If Required & Weather Dependant

Please Note:-
 All subject to weather conditions and site variations which may cause programme of works variations.
 Hours of work to be Mon - Fri 8.00am - 5.00pm Unless agreed with client

