



SECURITY FENCE

DEVELOPMENT BOUNDARY

INVERTER

MAIN CABLE TRENCH AND MAINTENANCE ROAD

DNO

This drawing is copyright of Green Switch Solutions Ltd and its use or reproduction without the written permission of Green Switch Solutions Ltd is prohibited.
 Due to unavoidable inaccuracies during the reproduction process these drawings should not be used for legal purposes. Dimensions are subject to Green Switch Solutions Ltd. considerations should be requested to confirm dimensions based on site survey information.
 All dimensions and quantities should be checked on site. Any discrepancy should be reported to Green Switch Solutions Ltd before any work commences.

LEGEND

	Total area
	Fence
	Main cable trench and Maintenance road

NOTES

PLANT POWER:
 4,903kWp
 20,340 modules

FENCE AREA:
 80,091.02m²

FENCE LENGTH:
 1,404m

TOTAL AREA:
 147,145.74m²

MODULES:
 Trina TSMG-240W
 Dimensions: 1660x816x45
 All panels due south facing

INVERTERS:
 TBC

STRUCTURES:
 Pitch of the Panels 25 degree (2x Portrait)

REV	REVISION DETAIL	BY	APV	DATE
-	-	-	-	-

Green Switch SOLUTIONS

Green Switch Solutions Ltd
 501 Meritt Park
 Riggall Road
 Burscough
 Lancashire L40 8JY
 www.greenswitchsolutions.co.uk
 TEL: 0845 643052

PROJECT
 Heapey Solar Park -
 Layout

STATUS
 DRAFT

DRAWING NO.	DATE	SCALE
DT1	TS 21/07/14	1:1000@A0

DRAWING No.	REVISION
GRNSS1037-A-02-u	2

